

PROJECT NOTES:

1. CONTACTOR SHALL MAINTAIN MINIMUM 24" CLEARANCE FROM ALL EXISTING UTILITIES.
2. FOR PUBLIC WATER & WASTEWATER LINE EMERGENCIES, CONTACT THE CITY OF LEANDER PUBLIC WORKS EMERGENCY 24-HOUR ON-CALL LINE AT 512-690-4760.
3. THE CONTRACTOR SHALL CONTACT THE TEXAS EXCAVATION SAFETY SYSTEM AT 1-800-344-8377 FOR EXISTING UTILITY LOCATIONS 48 HOURS PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UTILITIES THAT ARE TO BE EXTENDED, TIED TO, CROSSED, OR ALTERED; OR SUBJECT TO DAMAGE/INCONVENIENCE BY THE CONSTRUCTION OPERATIONS.
4. CONTACT THE CITY OF LEANDER PUBLIC WORKS DEPARTMENT FOR EXISTING WATER, WASTEWATER, STREET LIGHT ELECTRICAL WIRING, AND TRAFFIC SIGNAL WIRING LOCATIONS A MINIMUM OF 48 HOURS PRIOR TO START OF CONSTRUCTION.
 - a. LOCATE REQUESTS **MUST INCLUDE A COPY OF YOUR 811 TICKET.**
 - b. **REFRESH ALL LOCATES BEFORE 14 DAYS** – LOCATE REFRESH REQUESTS MUST INCLUDE A COPY OF YOUR 811 TICKET. TEXAS PIPELINE DAMAGE PREVENTION LAWS REQUIRE THAT A LOCATE REFRESH REQUEST BE SUBMITTED BEFORE 14 DAYS, OR IF LOCATION MARKERS ARE NO LONGER VISIBLE.
 - c. **REPORT ALL DAMAGE TO CITY INFRASTRUCTURE IMMEDIATELY** – IF YOU WITNESS OR EXPERIENCE EXCAVATION DAMAGE, PLEASE CONTACT THE CITY OF LEANDER PUBLIC WORKS DEPARTMENT BY PHONE. IF DAMAGE IS WITNESSED OR EXPERIENCED AFTER HOURS, CALL THE CITY OF LEANDER UTILITIES ON-CALL LINE AT THE NUMBER LISTED ABOVE.
5. A PRECONSTRUCTION CONFERENCE SHALL BE HELD WITH THE CONTRACTOR, DESIGN ENGINEER/PERMIT APPLICANT & CITY OF LEANDER REPRESENTATIVES PRIOR TO INSTALLATION OF EROSION/SEDIMENTATION CONTROLS & TREE PROTECTION MEASURES AS WELL AS PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE CITY OF LEANDER PLANNING DEPARTMENT AT 512-528-2750 AT LEAST THREE (3) DAYS PRIOR TO MEETING DATE.
6. CITY OF LEANDER NOISE ORDINANCE PROHIBITS CONSTRUCTION ACTIVITY BETWEEN THE HOURS OF 9 PM AND 7 AM. REQUESTS FOR EXCEPTIONS TO THE ORDINANCE MUST BE MADE TO LEANDER CITY COUNCIL.
7. CONTRACTOR SHALL BORE UNDER ALL DRIVEWAYS, STREET CROSSINGS AND OTHER PAVED AREAS. OPEN CUT CROSSING SHALL NOT BE ALLOWED.
8. CONTRACTOR SHALL REPLACE ALL DAMAGED PAVEMENT, CURB & GUTTER, SIDEWALK, CURB INLETS AND ALL OTHER INFRASTRUCTURE DAMAGED BY CONSTRUCTION PER CITY OF LEANDER STANDARDS & SPECIFICATIONS.
9. THE CURRENT COMPANIES THAT HOLD CONTRACTS WITH THE CITY FOR WASTE HAULING ARE AL CLAWSON DISPOSAL, INC., ARROW ROLL OFF'S AND RECYCLING, BIN DUMPED, HOOK N HAUL, CENTRAL WASTE & RECYCLING, CENTRAL TEXAS REFUSE, LOSSEN BROTHERS CONSTRUCTION, RECON SERVICES, LIBERTY DUMPSTER REMOVAL, TEXAS DISPOSAL SYSTEM.

10. ALL UNDERGROUND UTILITY LINES SHALL CROSS UNDERNEATH WATERLINES.
11. THE MINIMUM DEPTH OF COVER FOR UTILITY LINES INSTALLED UNDER CITY OF LEANDER ROADWAYS SHALL BE 36" BENEATH FINISHED GRADE.

EROSION CONTROL & RESTORATION:

1. THE CITY OF LEANDER ENVIRONMENT INSPECTOR HAS THE AUTHORITY TO ADD OR MODIFY EROSION/SEDIMENTATION CONTROLS ON SITE THROUGHOUT THE DURATION OF THE PROJECT.
2. ALL AREAS DISTURBED OR EXPOSED DURING CONSTRUCTION SHALL BE RESTORED WITH A MINIMUM OF 6" TOPSOIL. THE 6" MINIMUM SOIL DEPTH SHALL CONSISTS OF 75% SOIL BLENDED WITH 25% COMPOST.
3. ALL DISTURBED AREAS SHALL BE RE-VEGETATED USING ONLY APPROVED GRASSES FROM THE GROW GREEN GUIDE.