



2700 EARL RUDDER FWY. S.  
SUITE 4000  
COLLEGE STATION, TEXAS 77845  
979-694-1791  
FAX 694-8293  
WWW.BRWARCH.COM

## ADDENDUM NO. 3

### LEANDER UTILITY CUSTOMER SERVICE AREA RENOVATION LEANDER, TEXAS

DATE: July 13, 2015  
PROJECT NO: 214067.00

The Construction Documents on the above referenced project, dated 05/20/2015, shall be revised as follows:

#### SPECIFICATIONS:

**Item No. 1** (RE: SPECIFICATON SECTION 01 23 00) ALTERNATES: The alternates, as shown in Specification Section 01 23 00-2 are identified in reverse. Alternates shall read:

Alternate No. 1: Add storefront vestibule as shown in alternate floor plan, including storefront windows and entry.

Alternate No. 2: Remove and Replace existing exterior storefront as noted in floor plans.

**Item No. 2** (RE: INTERIOR WALL MOUNTED DROP BOX) The interior Wall Mount Drop Box, as shown on wall adjacent to walk up service desk shall be equal to Locking Security Mailbox, Wall Mount Drop Slot, Item # S3355. Slot shall have custom engraving indicating "Drop Box" in black lettering. The Optional Receptacle shall be included with the Drop Slot. Drop Box shall be constructed of ¼" aluminum plate and 20 gauge steel. Color: Bronze.

**Item No. 3** (RE: EXTERIOR IN-WALL MOUNTED DROP BOX) The exterior In-Wall (Through the Wall) locking drop box shall be equal to: Locking Security Mailbox Adjustable Through the Wall Locking Drop Box, SKU: PSWDC160. The drop box shall have a double steel door with lock guard. The Slot shall include a security baffle and an adjustable chute, to adjust for wall thickness. The drop box shall be located on the exterior wall of the storage room, location as denoted by keynote 1490.04 on Detail 2/A1.1.

#### DRAWINGS:

**Item No. 4** (RE: ALARM BELL): The existing alarm bell shall be replaced with a Wireless Motion Detector. New alarm bell and motion detector shall be equal to Milton's Wireless Motion Detector Chime Kit. Sensor shall have a sensitivity adjustment for control of depth of monitoring. The chime shall have a built in volume control. Location of sensor shall be as shown on Drawing Sheet A1.1 and denoted by keynote 2620.16 on Detail 2/A1.1

**Item No. 5** (RE: SOLID CORE WOOD DOOR) PL1: Door Type C shall have a plastic laminate finish, as noted in Door Schedule. The plastic laminate, as denoted by PL1 on the Door Schedule, shown on Drawing Sheet A2.1 and in the Finish Schedule, shown on Drawing Sheet A3.2 shall be Wilsonart 7935K-07 Shaker Cherry.

**Attachments: None**

END OF ADDENDUM NO.3\*\*\*\*\*