



**REQUEST FOR PROPOSAL
UNDERGROUND FIBER OPTIC CABLE INSTALLATION
ADDENDUM #1**

RFP No. 15-025

Addendum No. 1

Date of Addendum: August 21, 2015

Please note the clarification and/or additional information for the solicitation referenced above.

- 1. Q: What size conduit is to be installed?**

A: Standard 4" conduit shall be installed with three (3) 1 1/4" corrugated innerducts.
- 2. Q: What conduit is existing for the ISD?**

A: Standard 4" conduit is in place at the ISD locations. Where innerduct is not in place, two (2) or three (3) 1 1/4" corrugated innerducts are required as applicable.
- 3. Q: Where will the buildings be penetrated?**

A: Buildings shall be penetrated at the attack level using innerduct.
- 4. Q: What about Maxcell?**

A: Maxcell is acceptable.
- 5. Q: Does City require under-street boring or can the streets be cut?**

A: City requires under-street boring. No open cut asphalt cutting shall be permitted.
- 6. Q: Will permits be required and if so will fees be waived?**

A: No permits will be required for this project.
- 7. Q: How deep are the trenches required to be?**

A: A minimum of 30" of cover is required.
- 8. Q: Are there any improvements planned to Bagdad Road near City Hall.**

A: No. Not in the foreseeable future.
- 9. Q: Does the City require standard SC connection for the splice?**

A: Yes.
- 10. Q: Where is the MDF?**

A: City Hall, the Parks building and the Public Works building will require boxes. City Hall terminates at the rack. The ISD terminates at the source.
- 11. Q: Will wall mounts be required at the Parks building and Public Works building?**

A: Yes.

12. Q: Does the City have a brand preference?
A: No.
13. Q: Does the City require the 4-hour response time for response and repair to the system?
A: Yes, at a minimum.
14. Q: Can the City provide the measurements for the easements?
A: The installation is to take place in the Right-of-Way. No easement is needed.
15. Q: What hours can work be performed?
A: Standard project working hours per ordinance are 7 AM to 9 PM, 7 days a week.
16. Q: Will there be access to water for drilling?
A: City cannot guarantee access to water.
17. Q: How much slack shall be provided at each manhole?
A: 50 feet of slack shall be provided at each manhole.
18. Q: Does City require each cable to be labeled at each entry point?
A: Yes. Successful respondent shall label each cable at the entry points with City of Leander identification using durable tags with a zip tie or something similar.
19. Q: Who will be providing the locates during the five-year maintenance window?
A: Successful respondent shall place tracer wire on top of (outside) of conduit. City of Leander can then provide locates as needed.
20. A: Q: Does the City require outside plant (OSP) armored cable?
A: Yes.



Approved by _____
Joy Simonton, Purchasing Agent

By the signatures affixed below, Addendum No. 1 is hereby incorporated into and made a part of the above referenced solicitation.

ACKNOWLEDGED

Vendor

Authorized Signature

Date

RETURN ONE COPY SIGNED COPY OF THIS ADDENDUM TO THE PURCHASING OFFICE WITH YOUR SEALED PROPOSAL. FAILURE TO DO SO MAY AUTOMATICALLY DISQUALIFY YOUR RESPONSE FROM CONSIDERATION FOR AWARD.